

CONTRACTOR SHALL FURNISH MATERIALS, EQUIPMENT, SUPPLIES AND LABOR TO REMOVE, DISPOSE OF EXISTING DOCK AND INSTALL REPLACEMENT DOCK AT DRY BOAT STORAGE AREA , PICKWICK LANDING STATE PARK ; P.O. BOX 15 PICKWICK DAM, TN 38365

PROJECT TO BE COMPLETED WITHIN 60 CALENDAR DAYS AFTER RECEIVING PURCHASE ORDER AND NOTICE TO PROCEED.

CONTRACTOR SHALL KNOW AND IMPLEMENT CODES AND SAFETY REGULATIONS RELATED TO PROJECT.

CONTRACTOR SHALL PROVIDE LABOR & EQUIPMENT TO REMOVE AND DISPOSE OF OLD PART OF EXISTING DOCK AND SHALL ATTACH NEW PART OF EXISTING DOCK TO REPLACEMENT DOCK. OFFLOAD AND INSTALL REPLACEMENT DOCK. CONTRACTOR SHALL CONTACT PARK MANAGEMENT TO DETERMINE CONNECTING METHOD OF NEW AND USABLE PART OF EXISTING DOCK. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO OBTAIN REQUIRED PERMITS AND PAY FEES SCHEDULE INSPECTIONS OR APPROVALS. USE OF EXISTING GANGWAY FRAMEWORK AND SPUD POLES PERMITTED. CONTRACTOR SHALL BE RESPONSIBLE FOR PROPERLY FASTENING AND PLACEMENT OF DOCK TO EXISTING GANGWAY. SHALL REPLACE EXISTING GANGWAY FLOORING WITH PRESSURE TREATED 2X6 TIMBERS MAXIMUM ¼" SPACING BETWEEN BOARDS AND PROPERLY FASTEN. UTILITIES ON EXISTING DOCK SHALL BE REPLACED WITH NEW MATERIALS TO SAME LOCATION ON REPLACEMENT DOCK IN COMPLIANCE TO LOCAL, STATE AND FEDERAL LAWS OR CODES. WATER SUPPLY LINES SHALL BE RAN IN PEX PIPING. CONTRACTOR SHALL DEMO EXISTING CONCRETE PAD AND POUR NEW PAD TO MATCH EXISTING IN SIZE WITH ½" REBAR GRID, 4,000 PSI MIX, MINIMUM 4" IN THICKNESS AT ENTRANCE OF GANGWAY. GANGWAY SHALL BE ATTACHED TO PAD AND REPLACEMENT DOCK.

REPLACEMENT DOCK DESCRIPTION

(1) 8' X 92' MAINWALK

(4) 4' X 24' OPEN FINGERS

GALVANIZED STEEL FRAMES

POLYETHYLENE FLOATS

CONCRETE DECK PANELS – EXPOSED ROCK AGGREGATE FINISH, 4000 PSI

NO UNDERWATER TRUSS SYSTEM

PIPE PILING ANCHORAGE SYSTEM

(2) 6" X 5' PIPE PILE SLEEVES FOR USE WITH EXISTING PILING

BUMPERING/FENDERING

SINGLE ROW 2" X 6" TREATED SOUTHERN YELLOW PINE SIDEWOOD ON PERIMETER
BLACK #5001 VINYL BUMPER ON PERIMETER AND BLACK 6" CORNER BUMPERS

ATTACHED WITH STAINLESS STEEL STAPLES

MOORING DEVICES – (30) 10" ALUMINUM SIDE MOUNT CLEATS

MANUFACTURE WARRANTIES

TWO YEAR MANUFACTURER'S MATERIAL LIMITED WARRANTY

FIVE YEAR MANUFACTURER'S CONCRETE DECKING MATERIAL LIMITED WARRANTY

TEN YEAR MANUFACTURER'S FLOTATION LIMITED WARRANTY

QUALIFICATIONS

1. SCOPE AND SEQUENCE AS AGREED – SUPPLY AND SITE DELIVERY
2. PROVIDE ALL REQUIRED TOOLS, LABOR AND EQUIPMENT TO PERFORM SCOPE
3. REMOVAL AND DISPOSAL OF EXISTING DOCK
4. OFFLOADING AND PLACEMENT OF REPLACEMENT DOCK
5. DOCK INSTALLATION OF REPLACEMENT
6. PROVIDE PROTECTION OF EXISTING SURFACES AT WORK AREA, ALL WORK AREAS CLEANED DAILY

CONTRACTOR SHALL FIELD VERIFY TO PERSONAL SATISFACTION, SCOPE OF WORK, ACCESS, TOOLS, EQUIPMENT AND SKILL LEVEL NEEDED FOR IMPLEMENTATION OF PROJECT.

CONTRACTOR SHALL REPAIR AT NO COST TO AGENCY DAMAGE CAUSED BY CONSTRUCTION OR CONTRACTORS ACTIVITIES. REPAIRS SHALL BE COMPATABLE WITH ADJACENT AREA'S MATERIALS AND WORKMANSHIP.

CONTRACTOR SHALL COMPLY WITH LATEST EDITION OF LOCAL, STATE AND FEDERAL CODES, TRADE STANDARDS, REGULATIONS, SPECIFICATIONS AND AGENCY'S APPROVAL.

CONTRACTOR SHALL ATTEND AN ON SITE PRECONSTRUCTION CONFERENCE, PROGRESS MEETINGS AND FINAL INSPECTION, CONTACT: REID MULLINS, 731-968-6608 FOR DATE AND TIME OF MEETINGS.

CONTRACTOR SHALL MAINTAIN A CLEAN SAFE WORK SITE, REMOVE SCRAP AND UNUSED MATERIALS FROM STATE PROPERTY WHEN PROJECT IS COMPLETED LEAVING AREA IN A CLEAN CONDITION SUITABLE FOR INTENDED USE. A COPY OF SPECIFICATIONS SHALL BE ON SITE AND AVAILABLE WHEN WORK IS BEING PERFORMED.

CONTRACTOR SHALL WARRANTY MATERIALS AND WORKMANSHIP FOR A PERIOD OF ONE YEAR FROM DATE OF ACCEPTANCE.

PROPOSED REPLACEMENT DOCK DIMENSIONS

